
MRI Tranquility Overlay Lens 2x2

RECESSED





Project	
Type	
Notes	

TYPICAL INPUT WATTS

20 W/unit

* Based on a 2' x 2' luminaire using one remote driver

Lens overlays the grid to create a flush, minimalist appearance

- 2x2 (also available in 4x4)
- Extensive library of images to choose from
- · Non-ferrous, all aluminum construction
- · Decorative fasteners made of brushed aluminum
- Clean appearance when installed side-by-side fully concealing T-bars
- Ceiling grid: 15/16"











Ordering Guide

BCTQGMRI			22					90		40	
	PRODUCT ID	SIZE		CONFIGURATION			IMAGE *	CRI		COLOR TEMP.	
BCTQGMRI	Overlay Lens MRI Tranquility Series	22	2'X2'	2 3 4 9	one fixture two fixtures three fixtures four fixtures nine fixtures specify configuration - (#) fixtures*	PROCEED 1 CATALOGU PLACE)	CK HERE TO O IMAGE SELECTION E (INSERT CODE IN custom image*	90	90 CRI	40	4000 K
*Provide configuration drawing. Consult fact		iguration drawing. Consult factory.	* Provide your dpi at 100% in images specify	own image (must be 150 nage size). For multiple v as TQC(01), TQC(02)etc.							

FL							
SHIELDING POSITION			VOLTAGE	MOUNTING/SUSPENSION			
FL	flush	DC	24V (CV) low voltage		t-bar 15/16" t-bar 1 1/2" *		
		Provided Luminain compon	note driver I with 50 ft cord. DO NOT CUT. The is only compatible with ents specified for Remote upply enclosure. See the spec	* Consult factory - special order.			

Remote power supply ordered separately.

See Remote Power supply spec sheet.

© 2016 Axis Lighting Inc. 1.800.263.2947

[T] 514.948.6272



Tranquility Overlay Lens 2x2 RECESSED

SPECIFICATIONS

CONSTRUCTION

Housing 0.040" aluminum, nominal 18 gauge.

Optics 0.236" (6mm) PMMA lens with Tranquility

series image.

Reflectors Hi reflectance powder coat aluminum.

Luminaire support Aluminum hold-down clips

• FINISH

Powder coated paint.

CEILING SYSTEM

T-BAR STYLE MOUNTING (TB24) (TBI5) 15/16" T-BAR I 1/2" T-BAR

WEIGHT

2x2 14 lbs / 6.4 kg

APPROVALS

With product features that promote cleanability and durability, Axis Lighting meets functional and application-specific industry listings such as UL, and National Sanitation Foundation (NSF) standards. Independently tested and certified to meet MIL-Std 461-G for conducted and radiated emissions.

LED SYSTEM

CRI &CCT 90 CRI & 4000K have been selected as the color

> options that most enhance the broad spectrum range within the Tranquility graphics series that

will apply to this luminaire

LED life Minimum 50,000h with 85% of lumen

> maintenance in 25°C ambient temperature, in compliance with IES LM-80 testing

measurements.

Thermal Aluminum housing acting as the heat sink to

maximize life. Management

ELECTRICAL

DC 24 V constant voltage driver provided with 50 ft of cord with the MOLEX® Quick connect plug. (DO NOT CUT)

> Luminaire is ONLY compatible with components specified for remote power supply enclosure. See the spec sheet here.

QUICK CONNECT




Illustration shows cables that run from RPS to luminaire using MOLEX® Quick Connect plug for easy wiring.


! Please note that luminaire type will be clearly labeled both on the cable and on the luminaire plate in order to match correct cable to its respective luminaire and circuit.



8 eight fixtures configuration shown

CONFIGURATION

Standard configurations shown. For custom layout please provide configuration drawing, then consult factory.




EASY IMAGE SPECIFICATION STEPS

- 1. Select the luminaire.
- 2. Select your desired configuration.
- 3. Select image from our portfolio, or provide your own image (must be 150 dpi at 100% image size).
- 4. Send us your layout and we will prepare a proof for your final approval.



Select the luminaire.




Select your desired configuration.



Select image from our portfolio, or provide your own high resolution

image.



Send us your layout and we will prepare a proof for your final approval.

WARRANTY

Axis Lighting will warrant defective LEDs, boards, EMI filters and drivers for 5 years from date of purchase. Warranty is valid only if luminaire is installed and used according to specifications and installation instructions.


If defective, Axis will send replacement boards, filters or drivers at no cost along with detailed replacement instructions and instructions on how to return defective components to Axis.

Please fill out Specifier Acknowledgment and affirm that the MRI Installation Registration checklist will be provided to the installer to be completed, signed and returned to your respective Axis lighting Project Manager.


For warranty purposes please carefully read all supporting instructions, and make sure to follow them for the installation.

This Axis Lighting warranty will not go into effect until receipt of the signed Installation Registration Checklist (see last page).

EXAMPLE WIRING DIAGRAMS



Single connection installation



Multiple connection installation


See more details on wiring on RPS spec sheet.


• IMPORTANT SAFETY MEASURES


Power must be supplied by grounded Axis Remote Power Supply to ensure adequate EMI filtering. Remote power supply system must be ordered separately, and installed according to provided instructions. Please follow link for the RPS spec sheet.


- This product must be installed in accordance with the applicable installation code by a person familiar with the construction and operation of the product and the hazards involved in an MRI environment.
- Disconnect power to all circuits before wiring fixture.
- Install in accordance with all national, state, and local codes.
- Remote power supply box MUST be grounded
- Failure to install unit on a mechanically-sound surface may result in personal injury, physical damage, or potential fire hazard
- Use installation procedures appropriate for an environment involving MRI and sensitive electronic equipment.
- Read all fixture markings and labels to ensure correct installation of fixture
- Supplemental instructions may be located on the fixture, in addition to the instruction sheet provided with the shop drawing, regarding orientation, or mounting restrictions.


INSTALLATION INSTRUCTIONS














*SEE NEXT PAGE FOR FOLLOWING STEPS

© 2016 Axis Lighting Inc.


1.800.263.2947

[T] 514.948.6272



Tranquility Overlay Lens 2x2 RECESSED

*REST OF INSTALLATION PROCESS







Illustration shows cables that run from RPS to luminaire using MOLEX $^{\scriptsize\textcircled{\tiny{\$}}}$ Quick Connect plug for easy wiring.

! Please note that luminaire type will be clearly labeled both on the cable and on the luminaire plate in order to match correct cable to its respective luminaire and circuit.



CENTER LENS WITH T-BAR ALIGN 4 THUMBSCREWS IN CORNERS AND PARTIALLY THREAD

WHEN ALL THUMBSCREWS ARE ENGAGED, FULLY THREAD EACH EVENLY UNTIL LENS IS TIGHT AGAINST T-BAR

DO NOT OVER TIGHTEN

CENTRER LA LENTILLE DANS LA BORDURE DU PLACOPLÂTRE ALIGNEZ LES 4 VIS DE SERRAGE À MAIN ET FILETEZ PARTIELLEMENT CHAQUE VIS DE SERRAGE À MAIN UNE FOIS TOUTES LES VIS DE SERRAGE À MAIN ENGAGÉES, FILETEZ ENTIÈREMENT CHACUNE D'ELLES JUSQU'À CE QUE LA LENTILLE SOIT BIEN SERRÉE CONTRE LA BORDURE DE PLACOPLÂTRE

NE PAS TROP SERRER

*SEE NEXT PAGE FOR SPECIFIER ACKNOWLEDGMENT FORM

*SEE NEXT PAGE FOR MRI INSTALLATION REGISTRATION CHECKLIST

SPECIFIER ACKNOWLEDGMENT

Contractor acknowledges and understands the requirements of installing Axis Lighting products prior to the installation. Please sign below before Axis Lighting releases your order. Signature:_____ Date:_____ Project Name:_____ Print Name:_____ Send the form to your Axis Lighting Project Manager

MRI INSTALLATION REGISTRATION CHECKLIST

Customer acknowledges that attached Installation Registration Checklist will be provided to the installer to sign and return to Axis Lighting after the installation is complete.

Please fill out this form and return to your Axis Lighting Project Manager.

The warranty for your MRI installation will not go into effect until receipt of this signed registration checklist.

I certify that the lighting installation for the listed MRI suite is completed per the provided installation instructions and to the best of my abilities.

Please check off to denote status:

Installation instruction sheet for Remote Power Supply is read and followed.

Remote Power supply is located outside the shielded MRI exam room and grounded.

All dimming signals wiring is located outside the shielded MRI room.

Lighting system fully tested (including dimming operation if applicable) while MRI machine is in idle mode.

Lighting system fully tested (including dimming operation, if applicable) while MRI machine is in scan operation mode with the magnets fully activated.

If any of those steps cannot be completed or you need technical assistance, please contact Axis Lighting After Sales: at aftersalesteam@axislighting.com

Electrical Contractor	Installation site
Name:	Project Name:
Phone:	City / State (Province)
Installation date:	Send the form to your Axis Lighting Project Manager
Axis Lighting Project Manager: Date:	

